RELIANCE PROJECTS & PROPERTY MANAGEMENT SERVICES LIMITED
C/o Reliance Industries Ltd,, II floor, Trade Tower 94,
M.G.Marg Hazaratganj, Lucknow-226 001, UTTAR PRADESH, INDIA
Telephone : 9140955115
Email: Sunilkumar.Limbachia@ril.com

WORK ORDER

To 3267708 DIGITCOM INDIA TECHNOLOGIES 8 TH FLOOR 1082, ATS GREEN PARADISO GH 3 SECTOE CHI IV, GREATER NOIDA GAUTAM BUDDHA NAGAR UTTAR PRADESH Pin Code : 201310 INDIA Phone : 01204241387 Fax : E-Mail : MAYANK@DIGITCOMINDIA.COM Attention : MAYANK KUMAR GARG	Work Order No. : P16/630344992 Date : 06.03.2026 Contractor's Quot. Ref : Date : Our Ref : GSTN Of Biller : 09AEFPG4448D2ZN Bill From State : Uttar Pradesh Bill From : 3267708

This WORK ORDER, the SPECIAL CONDITIONS OF CONTRACT, the GENERAL CONDITIONS OF CONTRACT, the annexures enclosed to each of the foregoing, including any other document forming part of CONTRACT DOCUMENTS contain all the express terms and conditions of contract of supply of SERVICES ordered pursuant to this WORK ORDER and confirms and supersedes the LETTER OF COMMITMENT (if any) issued by COMPANY. CONTRACTOR agrees to supply the SERVICES, including all DELIVERABLES in full accordance with the foregoing terms and conditions. Capitalized terms used in this WORK ORDER but not defined in the WORK ORDER shall have the meaning ascribed to such terms in the foregoing SPECIAL CONDITIONS OF CONTRACT and GENERAL CONDITIONS OF CONTRACT. CONTRACTOR shall sign and return this WORK ORDER acknowledging the acceptance of this WORK ORDER within three (3) days of receipt at the communication address mentioned in this WORK ORDER. If acknowledgement is not received within three (3) days, this WORK ORDER will be deemed accepted by the CONTRACTOR. No other form of acceptance shall be binding on the PARTIES. For all future correspondence please quote this WORK ORDER NUMBER.

WO Period From DT : 06.03.2026
To DT : 31.12.2026

Value of Work	INR	39,880.00
CGST	INR	3,589.20
SGST	INR	3,589.20
TOTAL ORDER VALUE	**INR**	**47,058.40**

Value in Words :(Rs. Forty Seven Thousand Fifty Eight and Paise Forty only)
For other details, please refer line items.

Delivery Terms : N/A
Engineer in Charge :

Payment Terms : See Page Inside

BUYER : Singh	for RELIANCE PROJECTS & PROPERTY MANAGEMENT SERVICES LIMITED Authorised Signatory	CONTRACTOR'S Acceptance **Signature Title Date**

WORK ORDER

W.O.Number P16 / 630344992 Dt.06.03.2026

No	Item Code	Material/Work Description	Quantity	UOM	Price Details			Unit Rate	Amount (INR)
1		5G UBR_I&C_I-UE-BHNP-ENB-9062	1	AU					
					Value of Work		INR/AU		2,150.00
					CGST	9.00	%		193.50
					SGST	9.00	%		193.50
		Service Accounting Number: 998736							

The item covers the following Work :

10	3342265	CHRG TRANSPORT-UPTO 50KM-SCV-1 SITE MATL	1	EA - each			
					Net value of item	2,150.00	2,150.00

Transportation Charges for Free Issue Material (FIM) from W/H to the Site with SCV (Pickup or equivalent)#Charges are inclusive of Loading, Unloading, handling, Toll, etc.#This Service Code is applicable when Material of only One Site is carried in One Trip #(Rate per Site basis)

2		5G UBR_I&C_I-UE-BHNP-ENB-9062	1	AU					
					Value of Work		INR/AU		3,000.00
					CGST	9.00	%		270.00
					SGST	9.00	%		270.00
		Service Accounting Number: 998736							

The item covers the following Work :

10	3319645	CHRG EXTRA TRANSPORT. > 50 KM (PICKUP)	150	KM - Kilometer			
					Net value of item	20.00	3,000.00

EXTRA TRANSPORTATION COST BEYOND 50 KM FOR FIM MATERIAL FROM W/H TO SITE LOADING , UNLOADING, HANDLING ETC. WITH SMALL COMMERCIAL VEHICLE (PICKUP OR EQUIVALENT).#

3		5G UBR_I&C_I-UE-BHNP-ENB-9062	1	AU					
					Value of Work		INR/AU		2,790.00
					CGST	9.00	%		251.10
					SGST	9.00	%		251.10
		Service Accounting Number: 998736							

The item covers the following Work :

10	3339635	CHRG UBR LINK INSTALLATION & COMMISSIONI	1.000	LS - Lump Sum			
					Net value of item	2,790.00	2,790.00

UBR Link Installation & Commissioning inclusive of Installation AC &DC POE along with Surge and POE Laying and End Terminattion of Cat5/Cat6 cable, grouding cable(10 MM^2X1C/6 MM^2 X1C) and DC power cable(1.5 MM^2X2C and AC power Cable. All FIM (Rate per Hop). Details Mentioned Below.#1. Installing, fixing, assembling, interconnecting of ODU with mounting bracket if needed, PoE, Surge arrestor.#Termination of cables is part of TSP contractor scope#Installation : Pole/Wall mounting as per the guidelines of the site engineer#Material : UBR with accessories (wt. 4 Kg approx.) & IRM KIT (FIM: UBR equipments & IRM KIT)#2. Laying and routing of Cat 5 cable throgh Cable tray/conduit, connectorisation and termination of RJ-45 with ODU and PoE.#Average lenght of CAT 5 cable provided by vendor is of (FIM) 50m per site. #Termination of the cables is part of TSP contractor scope#Material : Crimping tool to be provided by vendor if required.#3. Laying, routing and termination of copper grounding cable. #Average lenght of Grounding cable provided by OEM is of 10m per site. #Termination of the cables is part of TSP contractor scope#Installation : Proper routing and termination of grounding cable as per guidelines.#Material : 1Core 6 AWG grounding cable (green color) of (FIM: 10MTR)#4. ermination of power cable to power on PoE, with compatiable connectorisation on site (AC or DC). Insulation and lebelling for terminated power cable in utility rack. #Material : For DC Supply : UV, non-armoured 2-core 14 AWG, black color, (FIM: 5MTR) #For AC Supply : non-armoured with 3 pin connector, (FIM: 3MTR)#5. Commissioning of ODU and alignemnt to get desire RSL as per link engineering.#Configure the ODU & PoE to integrate with RJIL system successfully. #Material : Laptop to be provided by vendor.#(I&C to be done as per installation guideliens relased for the Products to be deployed)#

No	Item Code	Material/Work Description	Quantity	UOM	Price Details	Unit Rate			Amount (INR)
4		5G UBR_I&C_I-UE-BHNP-ENB-9062	1	AU					
					Value of Work			INR/AU	1,350.00
					CGST		9.00	%	121.50
					SGST		9.00	%	121.50
		Service Accounting Number: 998736							

The item covers the following Work :

10 3300733 CHRG: UBR LINK ACCEPTANCE 1 PAA - Pair

Net value of item 1,350.00 1,350.00

UBR LINK ACCEPTANCE##"1. COORDINATE WITH DATA TEAM TO MAKE THE UBR LINK VISIBLE IN EMS (ELEMENT MANAGEMENT SYSTEM).#2. CO-ORDINATE ACCEPTANCE TESTING SCHEDULE WITH RJIL (AS PER GUIDELINE).#3. TESTING ON ETHERNET EQUIPMENT (FIM) IF REQUIRED FOR ACCEPTANCE TESTING. (AS PER A STANDARD FIELD TEST /COMMISSIONING PROCEDURE)#4. INSTALLATION INSPECTION PERFORMED BY VENDOR AFTER NOTIFICATION BY RJIL OF SITE COMPLETION & PROVIDE A WRITTEN LIST OF DESCPREPENCIES IF ANY.#5. COMPLETE LABELING OF UBR LINK AS PER AGREED FORMAT AND PROCESS WITH RJIL.#6. PERFORM LINK ACCEPTANCE TESTING AS PER DEFINED PROCEDURE WITH THE HELP OF TABLET (TABLETS SHALL BE ARRANGED BY RJIL).#7. CLEAR PUNCH POINTS RAISED BY RJIL/QA TEAM.#8. SUBMIT ALL COMMISSIONING AND ACCEPTANCE TEST REPORTS, AS SPECIFIED IN THE ACCEPTANCE TEST SCHEDULE, TO RJIL FOR ACCEPTANCE OF THE UBR LINK."#

5		5G UBR_I&C_I-UE-BHNP-ENB-9062	1	AU					
					Value of Work			INR/AU	180.00
					CGST		9.00	%	16.20
					SGST		9.00	%	16.20
		Service Accounting Number: 998736							

The item covers the following Work :

10 3175648 LAYING PVC FLEX COPPER CABLE 1C X 6 MM2 20 M - Meter

Net value of item 9.00 180.00

Laying of flexible copper cable 1 core X 6 mm2(cable as FIM) in any background including conduits,trays,junction boxes etc.Cable to be of ISI marked & RIL approved make.Supply of conduits,trays/J.B to be paid separately.

6		5G UBR_I&C_I-UE-BLMP-ENB-9075	1	AU					
					Value of Work			INR/AU	2,150.00
					CGST		9.00	%	193.50
					SGST		9.00	%	193.50
		Service Accounting Number: 998736							

The item covers the following Work :

10 3342265 CHRG TRANSPORT-UPTO 50KM-SCV-1 SITE MATL 1 EA - each

Net value of item 2,150.00 2,150.00

Transportation Charges for Free Issue Material (FIM) from W/H to the Site with SCV (Pickup or equivalent)#Charges are inclusive of Loading, Unloading, handling, Toll, etc.#This Service Code is applicable when Material of only One Site is carried in One Trip #(Rate per Site basis)

7		5G UBR_I&C_I-UE-BLMP-ENB-9075	1	AU					
					Value of Work			INR/AU	4,000.00
					CGST		9.00	%	360.00
					SGST		9.00	%	360.00
		Service Accounting Number: 998736							

No	Item Code	Material/Work Description	Quantity	UOM	Price Details	Unit Rate	Amount (INR)

The item covers the following Work :

10	3319645	CHRG EXTRA TRANSPORT. > 50 KM (PICKUP)	200	KM	- Kilometer		
					Net value of item	20.00	4,000.00

EXTRA TRANSPORTATION COST BEYOND 50 KM FOR FIM MATERIAL FROM W/H TO SITE LOADING , UNLOADING, HANDLING ETC. WITH SMALL COMMERCIAL VEHICLE (PICKUP OR EQUIVALENT).#

8		5G UBR_I&C_I-UE-BLMP-ENB-9075	1	AU			
					Value of Work	INR/AU	2,790.00
					CGST 9.00	%	251.10
					SGST 9.00	%	251.10
		Service Accounting Number: 998736					

The item covers the following Work :

10	3339635	CHRG UBR LINK INSTALLATION & COMMISSIONI	1.000	LS	- Lump Sum		
					Net value of item	2,790.00	2,790.00

UBR Link Installation & Commissioning inclusive of Installation AC &DC POE along with Surge and POE Laying and End Terminattion of Cat5/Cat6 cable, grouding cable(10 MM^2X1C/6 MM^2 X1C) and DC power cable(1.5 MM^2X2C and AC power Cable. All FIM (Rate per Hop). Details Mentioned Below.#1. Installing, fixing, assembling, interconnecting of ODU with mounting bracket if needed, PoE, Surge arrestor.#Termination of cables is part of TSP contractor scope#Installation : Pole/Wall mounting as per the guidelines of the site engineer#Material : UBR with accessories (wt. 4 Kg approx.) & IRM KIT (FIM: UBR equipments & IRM KIT)#2. Laying and routing of Cat 5 cable throgh Cable tray/conduit, connectorisation and termination of RJ-45 with ODU and PoE.#Average lenght of CAT 5 cable provided by vendor is of (FIM) 50m per site. #Termination of the cables is part of TSP contractor scope#Material : Crimping tool to be provided by vendor if required.#3. Laying, routing and termination of copper grounding cable. #Average lenght of Grounding cable provided by OEM is of 10m per site. #Termination of the cables is part of TSP contractor scope#Installation : Proper routing and termination of grounding cable as per guidelines.#Material : 1Core 6 AWG grounding cable (green color) of (FIM: 10MTR)#4. ermination of power cable to power on PoE, with compatiable connectorisation on site (AC or DC). Insulation and lebelling for terminated power cable in utility rack. #Material : For DC Supply : UV, non-armoured 2-core 14 AWG, black color, (FIM: 5MTR) #For AC Supply : non-armoured with 3 pin connector, (FIM: 3MTR)#5. Commissioning of ODU and alignemnt to get desire RSL as per link engineering.#Configure the ODU & PoE to integrate with RJIL system successfully. #Material : Laptop to be provided by vendor.#(I&C to be done as per installation guideliens relased for the Products to be deployed)#

9		5G UBR_I&C_I-UE-BLMP-ENB-9075	1	AU			
					Value of Work	INR/AU	1,350.00
					CGST 9.00	%	121.50
					SGST 9.00	%	121.50
		Service Accounting Number: 998736					

The item covers the following Work :

10	3300733	CHRG: UBR LINK ACCEPTANCE	1	PAA	- Pair		
					Net value of item	1,350.00	1,350.00

UBR LINK ACCEPTANCE##"1. COORDINATE WITH DATA TEAM TO MAKE THE UBR LINK VISIBLE IN EMS (ELEMENT MANAGEMENT SYSTEM).#2. CO-ORDINATE ACCEPTANCE TESTING SCHEDULE WITH RJIL (AS PER GUIDELINE).#3. TESTING ON ETHERNET EQUIPMENT (FIM) IF REQUIRED FOR ACCEPTANCE TESTING. (AS PER A STANDARD FIELD TEST /COMMISSIONING PROCEDURE)#4. INSTALLATION INSPECTION PERFORMED BY VENDOR AFTER NOTIFICATION BY RJIL OF SITE COMPLETION & PROVIDE A WRITTEN LIST OF DESCPREPENCIES IF ANY.#5. COMPLETE LABELING OF UBR LINK AS PER AGREED FORMAT AND PROCESS WITH RJIL.#6. PERFORM LINK ACCEPTANCE TESTING AS PER DEFINED PROCEDURE WITH THE HELP OF TABLET (TABLETS SHALL BE ARRANGED BY RJIL).#7. CLEAR PUNCH POINTS RAISED BY RJIL/QA TEAM.#8. SUBMIT ALL COMMISSIONING AND ACCEPTANCE TEST REPORTS, AS SPECIFIED IN THE ACCEPTANCE TEST SCHEDULE, TO RJIL FOR ACCEPTANCE OF THE UBR LINK."#

No	Item Code	Material/Work Description	Quantity	UOM	Price Details	Unit Rate			Amount (INR)
10		5G UBR_I&C_I-UE-BLMP-ENB-9075	1	AU					
					Value of Work			INR/AU	180.00
					CGST		9.00	%	16.20
					SGST		9.00	%	16.20
		Service Accounting Number: 998736							

The item covers the following Work :

10 3175648 LAYING PVC FLEX COPPER CABLE 1C X 6 MM2 20 M - Meter

Net value of item 9.00 180.00

Laying of flexible copper cable 1 core X 6 mm2(cable as FIM) in any background including conduits,trays,junction boxes etc.Cable to be of ISI marked & RIL approved make.Supply of conduits,trays/J.B to be paid separately.

11		5G UBR_I&C_I-UE-HRYA-ENB-9177	1	AU					
					Value of Work			INR/AU	2,150.00
					CGST		9.00	%	193.50
					SGST		9.00	%	193.50
		Service Accounting Number: 998736							

The item covers the following Work :

10 3342265 CHRG TRANSPORT-UPTO 50KM-SCV-1 SITE MATL 1 EA - each

Net value of item 2,150.00 2,150.00

Transportation Charges for Free Issue Material (FIM) from W/H to the Site with SCV (Pickup or equivalent)#Charges are inclusive of Loading, Unloading, handling, Toll, etc.#This Service Code is applicable when Material of only One Site is carried in One Trip #(Rate per Site basis)

12		5G UBR_I&C_I-UE-HRYA-ENB-9177	1	AU					
					Value of Work			INR/AU	3,000.00
					CGST		9.00	%	270.00
					SGST		9.00	%	270.00
		Service Accounting Number: 998736							

The item covers the following Work :

10 3319645 CHRG EXTRA TRANSPORT. > 50 KM (PICKUP) 150KM - Kilometer

Net value of item 20.00 3,000.00

EXTRA TRANSPORTATION COST BEYOND 50 KM FOR FIM MATERIAL FROM W/H TO SITE LOADING , UNLOADING, HANDLING ETC. WITH SMALL COMMERCIAL VEHICLE (PICKUP OR EQUIVALENT).#

13		5G UBR_I&C_I-UE-HRYA-ENB-9177	1	AU					
					Value of Work			INR/AU	2,790.00
					CGST		9.00	%	251.10
					SGST		9.00	%	251.10
		Service Accounting Number: 998736							

No	Item Code	Material/Work Description	Quantity	UOM	Price Details	Unit Rate	Amount (INR)

The item covers the following Work :

10	3339635	CHRG UBR LINK INSTALLATION & COMMISSIONI	1.000	LS	- Lump Sum		
					Net value of item	2,790.00	2,790.00

UBR Link Installation & Commissioning inclusive of Installation AC &DC POE along with Surge and POE Laying and End Terminattion of Cat5/Cat6 cable, grouding cable(10 MM^2X1C/6 MM^2 X1C) and DC power cable(1.5 MM^2X2C and AC power Cable. All FIM (Rate per Hop). Details Mentioned Below.#1. Installing, fixing, assembling, interconnecting of ODU with mounting bracket if needed, PoE, Surge arrestor.#Termination of cables is part of TSP contractor scope#Installation : Pole/Wall mounting as per the guidelines of the site engineer#Material : UBR with accessories (wt. 4 Kg approx.) & IRM KIT (FIM: UBR equipments & IRM KIT)#2. Laying and routing of Cat 5 cable throgh Cable tray/conduit, connectorisation and termination of RJ-45 with ODU and PoE.#Average lenght of CAT 5 cable provided by vendor is of (FIM) 50m per site. #Termination of the cables is part of TSP contractor scope#Material : Crimping tool to be provided by vendor if required.#3. Laying, routing and termination of copper grounding cable. #Average lenght of Grounding cable provided by OEM is of 10m per site. #Termination of the cables is part of TSP contractor scope#Installation : Proper routing and termination of grounding cable as per guidelines.#Material : 1Core 6 AWG grounding cable (green color) of (FIM: 10MTR)#4. ermination of power cable to power on PoE, with compatiable connectorisation on site (AC or DC). Insulation and lebelling for terminated power cable in utility rack. #Material : For DC Supply : UV, non-armoured 2-core 14 AWG, black color, (FIM: 5MTR) #For AC Supply : non-armoured with 3 pin connector, (FIM: 3MTR)#5. Commissioning of ODU and alignemnt to get desire RSL as per link engineering.#Configure the ODU & PoE to integrate with RJIL system successfully. #Material : Laptop to be provided by vendor.#(I&C to be done as per installation guideliens relased for the Products to be deployed)#

14	5G UBR_I&C_I-UE-HRYA-ENB-9177		1	AU			
					Value of Work	INR/AU	1,350.00
					CGST 9.00	%	121.50
					SGST 9.00	%	121.50
	Service Accounting Number:	998736					

The item covers the following Work :

10	3300733	CHRG: UBR LINK ACCEPTANCE	1	PAA	- Pair		
					Net value of item	1,350.00	1,350.00

UBR LINK ACCEPTANCE##"1. COORDINATE WITH DATA TEAM TO MAKE THE UBR LINK VISIBLE IN EMS (ELEMENT MANAGEMENT SYSTEM).#2. CO-ORDINATE ACCEPTANCE TESTING SCHEDULE WITH RJIL (AS PER GUIDELINE).#3. TESTING ON ETHERNET EQUIPMENT (FIM) IF REQUIRED FOR ACCEPTANCE TESTING. (AS PER A STANDARD FIELD TEST /COMMISSIONING PROCEDURE)#4. INSTALLATION INSPECTION PERFORMED BY VENDOR AFTER NOTIFICATION BY RJIL OF SITE COMPLETION & PROVIDE A WRITTEN LIST OF DESCPREPENCIES IF ANY.#5. COMPLETE LABELING OF UBR LINK AS PER AGREED FORMAT AND PROCESS WITH RJIL.#6. PERFORM LINK ACCEPTANCE TESTING AS PER DEFINED PROCEDURE WITH THE HELP OF TABLET (TABLETS SHALL BE ARRANGED BY RJIL).#7. CLEAR PUNCH POINTS RAISED BY RJIL/QA TEAM.#8. SUBMIT ALL COMMISSIONING AND ACCEPTANCE TEST REPORTS, AS SPECIFIED IN THE ACCEPTANCE TEST SCHEDULE, TO RJIL FOR ACCEPTANCE OF THE UBR LINK."#

15	5G UBR_I&C_I-UE-HRYA-ENB-9177		1	AU			
					Value of Work	INR/AU	180.00
					CGST 9.00	%	16.20
					SGST 9.00	%	16.20
	Service Accounting Number:	998736					

The item covers the following Work :

10	3175648	LAYING PVC FLEX COPPER CABLE 1C X 6 MM2	20	M	- Meter		
					Net value of item	9.00	180.00

Laying of flexible copper cable 1 core X 6 mm2(cable as FIM) in any background including conduits,trays,junction boxes etc.Cable to be of ISI marked & RIL approved make.Supply of conduits,trays/J.B to be paid separately.

No	Item Code	Material/Work Description	Quantity	UOM	Price Details	Unit Rate			Amount (INR)
16		5G UBR_I&C_I-UE-TLSP-ENB-9122	1	AU					
					Value of Work			INR/AU	2,150.00
					CGST		9.00	%	193.50
					SGST		9.00	%	193.50
		Service Accounting Number: 998736							

The item covers the following Work :

10	3342265	CHRG TRANSPORT-UPTO 50KM-SCV-1 SITE MATL	1	EA - each			
				Net value of item	2,150.00		2,150.00

Transportation Charges for Free Issue Material (FIM) from W/H to the Site with SCV (Pickup or equivalent)#Charges are inclusive of Loading, Unloading, handling, Toll, etc.#This Service Code is applicable when Material of only One Site is carried in One Trip #(Rate per Site basis)

17		5G UBR_I&C_I-UE-TLSP-ENB-9122	1	AU			
					Value of Work	INR/AU	4,000.00
					CGST	9.00 %	360.00
					SGST	9.00 %	360.00
		Service Accounting Number: 998736					

The item covers the following Work :

10	3319645	CHRG EXTRA TRANSPORT. > 50 KM (PICKUP)	200	KM - Kilometer			
					Net value of item	20.00	4,000.00

EXTRA TRANSPORTATION COST BEYOND 50 KM FOR FIM MATERIAL FROM W/H TO SITE LOADING , UNLOADING, HANDLING ETC. WITH SMALL COMMERCIAL VEHICLE (PICKUP OR EQUIVALENT).#

18		5G UBR_I&C_I-UE-TLSP-ENB-9122	1	AU			
					Value of Work	INR/AU	2,790.00
					CGST	9.00 %	251.10
					SGST	9.00 %	251.10
		Service Accounting Number: 998736					

The item covers the following Work :

10	3339635	CHRG UBR LINK INSTALLATION & COMMISSIONI	1.000	LS - Lump Sum			
					Net value of item	2,790.00	2,790.00

UBR Link Installation & Commissioning inclusive of Installation AC &DC POE along with Surge and POE Laying and End Terminattion of Cat5/Cat6 cable, grouding cable(10 MM^2X1C/6 MM^2 X1C) and DC power cable(1.5 MM^2X2C and AC power Cable. All FIM (Rate per Hop). Details Mentioned Below.#1. Installing, fixing, assembling, interconnecting of ODU with mounting bracket if needed, PoE, Surge arrestor.#Termination of cables is part of TSP contractor scope#Installation : Pole/Wall mounting as per the guidelines of the site engineer#Material : UBR with accessories (wt. 4 Kg approx.) & IRM KIT (FIM: UBR equipments & IRM KIT)#2. Laying and routing of Cat 5 cable throgh Cable tray/conduit, connectorisation and termination of RJ-45 with ODU and PoE.#Average lenght of CAT 5 cable provided by vendor is of (FIM) 50m per site. #Termination of the cables is part of TSP contractor scope#Material : Crimping tool to be provided by vendor if required.#3. Laying, routing and termination of copper grounding cable. #Average lenght of Grounding cable provided by OEM is of 10m per site. #Termination of the cables is part of TSP contractor scope#Installation : Proper routing and termination of grounding cable as per guidelines.#Material : 1Core 6 AWG grounding cable (green color) of (FIM: 10MTR)#4. ermination of power cable to power on PoE, with compatiable connectorisation on site (AC or DC). Insulation and lebelling for terminated power cable in utility rack. #Material : For DC Supply : UV, non-armoured 2-core 14 AWG, black color, (FIM: 5MTR) #For AC Supply : non-armoured with 3 pin connector, (FIM: 3MTR)#5. Commissioning of ODU and alignemnt to get desire RSL as per link engineering.#Configure the ODU & PoE to integrate with RJIL system successfully. #Material : Laptop to be provided by vendor.#(I&C to be done as per installation guideliens relased for the Products to be deployed)#

No	Item Code	Material/Work Description	Quantity	UOM	Price Details	Unit Rate			Amount (INR)
19		5G UBR_I&C_I-UE-TLSP-ENB-9122	1	AU					
					Value of Work			INR/AU	1,350.00
					CGST		9.00	%	121.50
					SGST		9.00	%	121.50
		Service Accounting Number: 998736							

The item covers the following Work :

10 3300733 CHRG: UBR LINK ACCEPTANCE 1 PAA - Pair

Net value of item 1,350.00 1,350.00

UBR LINK ACCEPTANCE##"1. COORDINATE WITH DATA TEAM TO MAKE THE UBR LINK VISIBLE IN EMS (ELEMENT MANAGEMENT SYSTEM).#2. CO-ORDINATE ACCEPTANCE TESTING SCHEDULE WITH RJIL (AS PER GUIDELINE).#3. TESTING ON ETHERNET EQUIPMENT (FIM) IF REQUIRED FOR ACCEPTANCE TESTING. (AS PER A STANDARD FIELD TEST /COMMISSIONING PROCEDURE)#4. INSTALLATION INSPECTION PERFORMED BY VENDOR AFTER NOTIFICATION BY RJIL OF SITE COMPLETION & PROVIDE A WRITTEN LIST OF DESCPREPENCIES IF ANY.#5. COMPLETE LABELING OF UBR LINK AS PER AGREED FORMAT AND PROCESS WITH RJIL.#6. PERFORM LINK ACCEPTANCE TESTING AS PER DEFINED PROCEDURE WITH THE HELP OF TABLET (TABLETS SHALL BE ARRANGED BY RJIL).#7. CLEAR PUNCH POINTS RAISED BY RJIL/QA TEAM.#8. SUBMIT ALL COMMISSIONING AND ACCEPTANCE TEST REPORTS, AS SPECIFIED IN THE ACCEPTANCE TEST SCHEDULE, TO RJIL FOR ACCEPTANCE OF THE UBR LINK."#

20		5G UBR_I&C_I-UE-TLSP-ENB-9122	1	AU					
					Value of Work			INR/AU	180.00
					CGST		9.00	%	16.20
					SGST		9.00	%	16.20
		Service Accounting Number: 998736							

The item covers the following Work :

10 3175648 LAYING PVC FLEX COPPER CABLE 1C X 6 MM2 20 M - Meter

Net value of item 9.00 180.00

Laying of flexible copper cable 1 core X 6 mm2(cable as FIM) in any background including conduits,trays,junction boxes etc.Cable to be of ISI marked & RIL approved make.Supply of conduits,trays/J.B to be paid separately.

Total Value of Work	INR	39,880.00
Total CGST	INR	3,589.20
Total SGST	INR	3,589.20
Total Order Value:	**INR**	**47,058.40**

Terms of payment :

Payment shall be made as per Detailed Payment Terms specified in the purchasing document.

Vendor will ensure that Tax Invoice is uploaded on EBIZ portal of Buyer within 7 days of its issue, Failure to upload the Tax Invoice within 7 days will be considered as non - submission of Invoice

It is mandatory for Seller to obtain Acceptance / Work Completion Certificate OR pdf copy of User confirmation obtained on email from Buyer's Representative / User and attach it along with invoice for this Order. Without this, Invoices submitted if any shall be treated as Invalid Invoice and shall be liable to be Rejected by Reliance with relevant information to contact person mentioned in this Order

Vendor Bank Details:
Bank Account No. : 105701601000515
Bank Name : UNION BANK OF INDIA
City : GAUTAM BUDDHA NAGAR

Liquidated Damages :

0.5 % PER WEEK TO MAX OF 5%

Document Submission Bank:

Note(S): 1. It is essential that the Contractor shall mention ItemNo. & Item code along with corresponding Material/Work Description and W.O.No. as mentioned above, in the Delivery challan (On-Shore Order), Measurement sheet and invoice for ease of material Inwarding, Certification of work and Bill Processing. Failure to do so may be the grounds for the rejections(s) or delay in release of payment(s).

PLANT REGISTRATION NO. : 09AAACR5055K1Z5

RELIANCE PROJECTS & PROPERTY MANAGEMENT SERVICES LIMITED
C/o Reliance Industries Ltd, II floor, Trade Tower 94,
M.G.Marg Hazaratganj, Lucknow-226 001, UTTAR PRADESH, INDIA
Telephone : 9140955115 Email: Sunilkumar.Limbachia@ril.com

Purchase Order

Number : P16/630344992
Date : 06.03.2026

BILL To ANNEXURE

Bill To Address : (Plant) JP79

RIL Proj-Uttar Pradesh (E),Reliance Industries Ltd.,,
8 and 9, PLOT NO TC 58V AND 59V,ELDECO CORPORATE,CHAMBER 2, PHASE 1,VIBHUTI KHAND, GOMTI NAGAR
Lucknow-226010
Uttar Pradesh,India
GSTIN:09AAACR5055K1Z5

POSrNo	Short Description
1	5G UBR_I&C_I-UE-BHNP-ENB-9062
2	5G UBR_I&C_I-UE-BHNP-ENB-9062
3	5G UBR_I&C_I-UE-BHNP-ENB-9062
4	5G UBR_I&C_I-UE-BHNP-ENB-9062
5	5G UBR_I&C_I-UE-BHNP-ENB-9062
6	5G UBR_I&C_I-UE-BLMP-ENB-9075
7	5G UBR_I&C_I-UE-BLMP-ENB-9075
8	5G UBR_I&C_I-UE-BLMP-ENB-9075
9	5G UBR_I&C_I-UE-BLMP-ENB-9075
10	5G UBR_I&C_I-UE-BLMP-ENB-9075
11	5G UBR_I&C_I-UE-HRYA-ENB-9177
12	5G UBR_I&C_I-UE-HRYA-ENB-9177
13	5G UBR_I&C_I-UE-HRYA-ENB-9177
14	5G UBR_I&C_I-UE-HRYA-ENB-9177
15	5G UBR_I&C_I-UE-HRYA-ENB-9177
16	5G UBR_I&C_I-UE-TLSP-ENB-9122
17	5G UBR_I&C_I-UE-TLSP-ENB-9122
18	5G UBR_I&C_I-UE-TLSP-ENB-9122
19	5G UBR_I&C_I-UE-TLSP-ENB-9122
20	5G UBR_I&C_I-UE-TLSP-ENB-9122

RELIANCE PROJECTS & PROPERTY MANAGEMENT SERVICES LIMITED
C/o Reliance Industries Ltd, II floor, Trade Tower 94,
M.G.Marg Hazaratganj, Lucknow-226 001, UTTAR PRADESH, INDIA
Telephone : 9140955115
Email: Sunilkumar.Limbachia@ril.com

Number P16 / 630344992
Date 06.03.2026

Additional terms and Conditions of the Work Order / Service Order / Contract Orders /Purchase Orders (hereinafter referred to as Order(s)).

This Order is being issued by Reliance Projects and Property Management Services Limited **("RPPMSL")** on behalf of Reliance Industries Limited **("RIL")** in favour of the entity referred to as Seller / Contractor / Service Provider/ Vendor as the case may be in the respective Order, subject to the following additional terms and conditions, which shall form an integral part of the Order.

1. Seller / Contractor / Service Provider/Vendor hereby agrees and acknowledges that pursuant to a Scheme of Arrangement between **Reliance Projects and Property Management Services Limited ("RPPMSL"/" Demerged Company") and Reliance Industries Limited ("RIL"/" Resulting Company")** and their respective shareholders and creditors, for demerger of Digital, Engineering, Procurement, and Construction**("EPC")**, Infrastructure and other businesses of **RPPMSL** into <B1 RIL on a going concern basis **("Scheme")** approved by Hon'ble NCLT, Mumbai and Ahmedabad respectively in proceedings under **C.P.(CAA)/194/MB/2023 in C.A. (CAA)/116/MB/2023 filed by RIL and Proceedings under CP(CAA)/21(AHM)2023 in CA(CAA)/34(AHM)2023 filed by RPPMSL,** the digital, EPC and infrastructure business of RPPMSL together with all relevant contracts, Orders are demerged and vested with RIL as a going concern with effect from the Effective Date specified in the Scheme.
2. As a matter of convenience and part of transition arrangement pursuant to a separate agreement entered between RIL & RPPMSL, this Order is being issued by RPPMSL on behalf of RIL and will be enforceable by RIL in any manner, in terms of the Order, without any further assignment in this regard.
3. Contractor shall ensure compliance of all applicable laws including applicable labour laws. If RPPMSL is required to bear any cost or consequences of any non-compliance of applicable laws or provisions of this Order by the Contractor / its Sub Contractor as applicable the same shall be recovered from the Contractor without any restriction or limitation.
4. Seller / Contractor / Service Provider / Vendor shall raise correct and complete invoices on RIL and submit all invoices together with necessary supporting(s) as per the terms of the Order and payment will be made by RIL as per the terms of Order. In case any invoices are already raised before RPPMSL after the effective date of the Scheme approved by NCLT, a revised invoice shall be raised on RIL and to be re-submitted along with all supporting documents as required.
5. These additional terms and conditions shall form an integral part of the Order and in case of any conflict between these terms and conditions and other terms and condition of the Order, these terms and conditions shall prevail.
6. In case any clarifications are required the Seller/ Contractor/ Vendor/ Service Provider shall approach RIL or Engineer In Charge (EIC)/ contract person of RIL specified in the Order, and the clarifications if any issued by RIL shall be final and binding on the Seller/ Contractor/ Service Provider/ Vendor.