RELIANCE PROJECTS & PROPERTY MANAGEMENT SERVICES LIMITED
C/o Reliance Industries Ltd,, II floor, Trade Tower 94,
M.G.Marg Hazaratganj, Lucknow-226 001, UTTAR PRADESH, INDIA
Telephone : 9140955115
Email: Ashwini1.Singh@ril.com

WORK ORDER

To 3267708 DIGITCOM INDIA TECHNOLOGIES 8 TH FLOOR 1082, ATS GREEN PARADISO GH 3 SECTOE CHI IV, GREATER NOIDA GAUTAM BUDDHA NAGAR UTTAR PRADESH Pin Code : 201310 INDIA Phone : 01204241387 Fax : E-Mail : MAYANK@DIGITCOMINDIA.COM Attention : MAYANK KUMAR GARG	Work Order No. : P16/630343554 Date : 19.02.2026 Contractor's Quot. Ref : Date : Our Ref : GSTN Of Biller : 09AEFPG4448D2ZN Bill From State : Uttar Pradesh Bill From : 3267708

This WORK ORDER, the SPECIAL CONDITIONS OF CONTRACT, the GENERAL CONDITIONS OF CONTRACT, the annexures enclosed to each of the foregoing, including any other document forming part of CONTRACT DOCUMENTS contain all the express terms and conditions of contract of supply of SERVICES ordered pursuant to this WORK ORDER and confirms and supersedes the LETTER OF COMMITMENT (if any) issued by COMPANY. CONTRACTOR agrees to supply the SERVICES, including all DELIVERABLES in full accordance with the foregoing terms and conditions. Capitalized terms used in this WORK ORDER but not defined in the WORK ORDER shall have the meaning ascribed to such terms in the foregoing SPECIAL CONDITIONS OF CONTRACT and GENERAL CONDITIONS OF CONTRACT. CONTRACTOR shall sign and return this WORK ORDER acknowledging the acceptance of this WORK ORDER within three (3) days of receipt at the communication address mentioned in this WORK ORDER. If acknowledgement is not received within three (3) days, this WORK ORDER will be deemed accepted by the CONTRACTOR. No other form of acceptance shall be binding on the PARTIES. For all future correspondence please quote this WORK ORDER NUMBER.

WO Period From DT : 19.02.2026
To DT : 31.12.2026

Value of Work	INR	51,475.00
CGST	INR	4,632.75
SGST	INR	4,632.75
TOTAL ORDER VALUE	**INR**	**60,740.50**

Value in Words :(Rs. Sixty Thousand Seven Hundred Forty and Paise Fifty only)

For other details, please refer line items.

Delivery Terms : N/A
Engineer in Charge :

Payment Terms : See Page Inside

BUYER : Singh	for RELIANCE PROJECTS & PROPERTY MANAGEMENT SERVICES LIMITED Authorised Signatory	CONTRACTOR'S Acceptance **Signature Title Date**

WORK ORDER

W.O.Number P16 / 630343554 Dt.19.02.2026
Page No: 1

No	Item Code	Material/Work Description	Quantity	UOM	Price Details			Unit Rate	Amount (INR)
1		A6 I&C_I-UE-ORAI-ENB-9005	1	AU					
					Value of Work			INR/AU	8,567.00
					CGST	9.00	%		771.03
					SGST	9.00	%		771.03
		Service Accounting Number: 998736							

The item covers the following Work :

10 3367739 CHRG ATP-11A - WIFI A6 DEPLOYMENT 1 EA - each
Net value of item 750.00 750.00

Charges for Installation & Commissioning (ATP-11A) Acceptance and Site CMM (Chief Maintenance Manager) Handover using tools provided as per the guidelines of engineer in charge along with 100% compliance and completion with as built drawings, testing and commissioning reports as per the requirement [ATP = Acceptance Test Procedure]##a. Charges for field acceptance (ATP-11A/C) using the assigned tools.#b. Capturing of the Radio installation pictures along with its exact location.#c. Power and grounding cable laying and termination to be captured.#d. weather proofing at radio end to be captured#e. Charges for execution of commissioning tests (ATP-11C) using the assigned tools.#f. Throughput/Ping and Latency Tests to be carried at each Radio.#g. CMM Handover to be carried within 30 days of Site ATP-11A completion for milestone closure#h. The rate shall include the cost of manpower, all software & hardware tools and tackles, required to execute the job.#i. Scope includes Site mobilization charges#* In case of deviation, NPE approval required for any additional vendor support required.#**Milestone closure can only be acceptable post completion and relevant approvals. All changes post rejection need to be closed within the scope requirement without any additional charges"#(The Unit of Measurement is "Per Site basis")

20 3383067 CHRG APPLY PUFF SEALENT AT CABLE ENTRY 1 EA - each
Net value of item 350.00 350.00

Charges for supply & applying of Puff Sealant of approved make on DC Power Cable and CIPRI Cable entry point (Roxtec or equivalent). #The Puff Sealant should be applied properly as per the instructions of the Engineer in Charge to ensure avoidance of any seepage.#(UoM : Nos of cable entry Points)

30 3367713 CHRG ATP-11C - WIFI A6 DEPLOYMENT 1 EA - each
Net value of item 750.00 750.00

Charges for Installation & Commissioning (ATP-11C) Acceptance and Site CMM (Chief Maintenance Manager) Handover using tools provided as per the guidelines of engineer in charge along with 100% compliance and completion with as built drawings, testing and commissioning reports as per the requirement [ATP = Acceptance Test Procedure]##a. Charges for field acceptance (ATP-11A/C) using the assigned tools.#b. Capturing of the Radio installation pictures along with its exact location.#c. Power and grounding cable laying and termination to be captured.#d. weather proofing at radio end to be captured#e. Charges for execution of commissioning tests (ATP-11C) using the assigned tools.#f. Throughput/Ping and Latency Tests to be carried at each Radio.#g. CMM Handover to be carried within 30 days of Site ATP-11A completion for milestone closure#h. The rate shall include the cost of manpower, all software & hardware tools and tackles, required to execute the job.#i. Scope includes Site mobilization charges#* In case of deviation, NPE approval required for any additional vendor support required.#**Milestone closure can only be acceptable post completion and relevant approvals. All changes post rejection need to be closed within the scope requirement without any additional charges"#(The Unit of Measurement is "Per Site basis")

40 3269867 TERMINATION OF CABLE 1CX6 SQMM Y 4.000 NOS - No.
Net value of item 48.00 192.00

TERMINATION OF 1CX6 SQMM Y.AS PER SYSTEM REQUIREMENT.,
SLEEVING,
FERRULING, TAGGING AS PER STANDARD TELECOM PRACTICES.

50 3317347 SITC 1CX6 SQMM CU CBL YY FRLSH 5 M - Meter
Net value of item 75.00 375.00

"SUPPLY, INSTALLATION, TESTING & COMMISSIONING OF ELECTRICAL CABLES WITH NECESSARY HARDWARES LIKE CLAMPS, CABLE TYE, GLANDS, LUGS, IDENTIFICATION TAGS ETC. #TYPE OF CABLE : 1CX6 SQMM CU CBL YY FRLSH.

60 3137158 LAYING-2CX2.5SQMM COPPER FLEXIBLE CABLE 60 M - Meter
Net value of item 15.00 900.00

Laying of 2Cx2.5Sqmm copper flexible cable

70 3367548 CHRG LAY & ROUTING-MULTIMODE FIBER CABLE 60 M - Meter
Net value of item 5.00 300.00

Laying and routing of MultiMode fiber cable through Cable tray and termination of pigtail with SFP on Radio and L2 switch optical port#FIM -Average length of Multi Mode armoured fiber cable provided by OEM is 50 to 100m per site. RJIO will provide 10G SFP to connect at Radio and L2 switch end.#Termination of the cables is part of TSP contractor scope#Material : Crimping tool to be provided by vendor if required."

No	Item Code	Material/Work Description	Quantity	UOM	Price Details	Unit Rate	Amount (INR)
80	3367489	CHRG BASE RADIO INST&COMS AZIMUTH	1	EA	- each		
					Net value of item	250.00	250.00

Base Station Radio Installation & Commissioning inclusive of DC power cable and Multimode armoured fiber cable , grounding cable laying and End Termination of MM armoured fiber cable with SFP both end , grounding cable(6 MM^2 X1C) and DC power cable(2CX14 AWG) . All FIM and Details Mentioned Below.#Installing, fixing, assembling, interconnecting of Base radio with mounting bracket at recommended height and Azimuth as per RJIO guideline. Base radio shall be installed on RJIO tower infra or building terrace pole mount.#Commissioning of Base radio and tilt/ alignment to get desire RSL as per link engineering.#Configure the BS Radio to integrate with RJIL EMS system successfully. #Proper weather proofing to be applied on all cable connectors at Radio end.#Material : Laptop to be provided by vendor (Required till ZTP is ready)#(I&C to be done as per installation guidelines released for the Products to be deployed)#BS Radio dimension : H490xW295xD75mm , weight : 4Kg #Termination of cable and SFP is part of deployment vendor scope#Material : Base Radio with accessories (wt. 4 Kg approx.) & IRM KIT (FIM: UBR Equipments & IRM KIT)"

90	3397253	CHRG EXTRA TRANSPORT CHRG>50 KM (PICKUP)	160	KM	- Kilometer		
					Net value of item	20.00	3,200.00

EXTRA TRANSPORTATION COST BEYOND 50 KM FOR FIM MATERIAL FROM W/H TO SITE LOADING , UNLOADING, HANDLING ETC. WITH SMALL COMMERCIAL VEHICLE (PICKUP OR EQUIVALENT).

100	3397271	CHRG TRANSPORT-UPTO 50KM-SCV-2-3SITE MAT	1	EA	- each		
					Net value of item	1,500.00	1,500.00

Transportation Charges for Free Issue Material (FIM) from W/H to the Site with SCV (Pickup or equivalent).Charges are inclusive of Loading, Unloading, handling, Toll, etc.This Service Code is applicable when Material of Multiple (2-3) Sites is carried in One Trip(Rate per Site basis)

2	A6 I&C_I-UE-SIKN-ENB-9031		1	AU			
					Value of Work	INR/AU	8,567.00
					CGST	9.00 %	771.03
					SGST	9.00 %	771.03
	Service Accounting Number:	998736					

The item covers the following Work :

10	3397271	CHRG TRANSPORT-UPTO 50KM-SCV-2-3SITE MAT	1	EA	- each		
					Net value of item	1,500.00	1,500.00

Transportation Charges for Free Issue Material (FIM) from W/H to the Site with SCV (Pickup or equivalent).Charges are inclusive of Loading, Unloading, handling, Toll, etc.This Service Code is applicable when Material of Multiple (2-3) Sites is carried in One Trip(Rate per Site basis)

20	3397253	CHRG EXTRA TRANSPORT CHRG>50 KM (PICKUP)	160	KM	- Kilometer		
					Net value of item	20.00	3,200.00

EXTRA TRANSPORTATION COST BEYOND 50 KM FOR FIM MATERIAL FROM W/H TO SITE LOADING , UNLOADING, HANDLING ETC. WITH SMALL COMMERCIAL VEHICLE (PICKUP OR EQUIVALENT).

30	3367489	CHRG BASE RADIO INST&COMS AZIMUTH	1	EA	- each		
					Net value of item	250.00	250.00

Base Station Radio Installation & Commissioning inclusive of DC power cable and Multimode armoured fiber cable , grounding cable laying and End Termination of MM armoured fiber cable with SFP both end , grounding cable(6 MM^2 X1C) and DC power cable(2CX14 AWG) . All FIM and Details Mentioned Below.#Installing, fixing, assembling, interconnecting of Base radio with mounting bracket at recommended height and Azimuth as per RJIO guideline. Base radio shall be installed on RJIO tower infra or building terrace pole mount.#Commissioning of Base radio and tilt/ alignment to get desire RSL as per link engineering.#Configure the BS Radio to integrate with RJIL EMS system successfully. #Proper weather proofing to be applied on all cable connectors at Radio end.#Material : Laptop to be provided by vendor (Required till ZTP is ready)#(I&C to be done as per installation guidelines released for the Products to be deployed)#BS Radio dimension : H490xW295xD75mm , weight : 4Kg #Termination of cable and SFP is part of deployment vendor scope#Material : Base Radio with accessories (wt. 4 Kg approx.) & IRM KIT (FIM: UBR Equipments & IRM KIT)"

40	3367548	CHRG LAY & ROUTING-MULTIMODE FIBER CABLE	60	M	- Meter		
					Net value of item	5.00	300.00

Laying and routing of MultiMode fiber cable through Cable tray and termination of pigtail with SFP on Radio and L2 switch optical port#FIM -Average length of Multi Mode armoured fiber cable provided by OEM is 50 to 100m per site. RJIO will provide 10G SFP to connect at Radio and L2 switch end.#Termination of the cables is part of TSP contractor scope#Material : Crimping tool to be provided by vendor if required."

50	3137158	LAYING-2CX2.5SQMM COPPER FLEXIBLE CABLE	60	M	- Meter		
					Net value of item	15.00	900.00

Laying of 2Cx2.5Sqmm copper flexible cable

No	Item Code	Material/Work Description	Quantity	UOM	Price Details	Unit Rate	Amount (INR)
60	3317347	SITC 1CX6 SQMM CU CBL YY FRLSH	5	M	- Meter		
					Net value of item	75.00	375.00

"SUPPLY, INSTALLATION, TESTING & COMMISSIONING OF ELECTRICAL CABLES WITH NECESSARY HARDWARES LIKE CLAMPS, CABLE TYE, GLANDS, LUGS, IDENTIFICATION TAGS ETC. #TYPE OF CABLE : 1CX6 SQMM CU CBL YY FRLSH.

70	3269867	TERMINATION OF CABLE 1CX6 SQMM Y	4.000	NOS	- No.		
					Net value of item	48.00	192.00

TERMINATION OF 1CX6 SQMM Y.AS PER SYSTEM REQUIREMENT.,
SLEEVING,
FERRULING, TAGGING AS PER STANDARD TELECOM PRACTICES.

80	3367739	CHRG ATP-11A - WIFI A6 DEPLOYMENT	1	EA	- each		
					Net value of item	750.00	750.00

Charges for Installation & Commissioning (ATP-11A) Acceptance and Site CMM (Chief Maintenance Manager) Handover using tools provided as per the guidelines of engineer in charge along with 100% compliance and completion with as built drawings, testing and commissioning reports as per the requirement [ATP = Acceptance Test Procedure]##a. Charges for field acceptance (ATP-11A/C) using the assigned tools.#b. Capturing of the Radio installation pictures along with its exact location.#c. Power and grounding cable laying and termination to be captured.#d. weather proofing at radio end to be captured#e. Charges for execution of commissioning tests (ATP-11C) using the assigned tools.#f. Throughput/Ping and Latency Tests to be carried at each Radio.#g. CMM Handover to be carried within 30 days of Site ATP-11A completion for milestone closure#h. The rate shall include the cost of manpower, all software & hardware tools and tackles, required to execute the job.#i. Scope includes Site mobilization charges#* In case of deviation, NPE approval required for any additional vendor support required.#**Milestone closure can only be acceptable post completion and relevant approvals. All changes post rejection need to be closed within the scope requirement without any additional charges"#(The Unit of Measurement is "Per Site basis")

90	3383067	CHRG APPLY PUFF SEALENT AT CABLE ENTRY	1	EA	- each		
					Net value of item	350.00	350.00

Charges for supply & applying of Puff Sealant of approved make on DC Power Cable and CIPRI Cable entry point (Roxtec or equivalent). #The Puff Sealant should be applied properly as per the instructions of the Engineer in Charge to ensure avoidance of any seepage.#(UoM : Nos of cable entry Points)

100	3367713	CHRG ATP-11C - WIFI A6 DEPLOYMENT	1	EA	- each		
					Net value of item	750.00	750.00

Charges for Installation & Commissioning (ATP-11C) Acceptance and Site CMM (Chief Maintenance Manager) Handover using tools provided as per the guidelines of engineer in charge along with 100% compliance and completion with as built drawings, testing and commissioning reports as per the requirement [ATP = Acceptance Test Procedure]##a. Charges for field acceptance (ATP-11A/C) using the assigned tools.#b. Capturing of the Radio installation pictures along with its exact location.#c. Power and grounding cable laying and termination to be captured.#d. weather proofing at radio end to be captured#e. Charges for execution of commissioning tests (ATP-11C) using the assigned tools.#f. Throughput/Ping and Latency Tests to be carried at each Radio.#g. CMM Handover to be carried within 30 days of Site ATP-11A completion for milestone closure#h. The rate shall include the cost of manpower, all software & hardware tools and tackles, required to execute the job.#i. Scope includes Site mobilization charges#* In case of deviation, NPE approval required for any additional vendor support required.#**Milestone closure can only be acceptable post completion and relevant approvals. All changes post rejection need to be closed within the scope requirement without any additional charges"#(The Unit of Measurement is "Per Site basis")

3		A6 I&C_I-UE-TLBT-ENB-9091	1	AU			
					Value of Work	INR/AU	14,967.00
					CGST 9.00	%	1,347.03
					SGST 9.00	%	1,347.03
		Service Accounting Number: 998736					

The item covers the following Work :

10	3397271	CHRG TRANSPORT-UPTO 50KM-SCV-2-3SITE MAT	1	EA	- each		
					Net value of item	1,500.00	1,500.00

Transportation Charges for Free Issue Material (FIM) from W/H to the Site with SCV (Pickup or equivalent).Charges are inclusive of Loading, Unloading, handling, Toll, etc.This Service Code is applicable when Material of Multiple (2-3) Sites is carried in One Trip(Rate per Site basis)

20	3397253	CHRG EXTRA TRANSPORT CHRG>50 KM (PICKUP)	480	KM	- Kilometer		
					Net value of item	20.00	9,600.00

EXTRA TRANSPORTATION COST BEYOND 50 KM FOR FIM MATERIAL FROM W/H TO SITE LOADING , UNLOADING, HANDLING ETC. WITH SMALL COMMERCIAL VEHICLE (PICKUP OR EQUIVALENT).

No	Item Code	Material/Work Description	Quantity	UOM	Price Details	Unit Rate	Amount (INR)
30	3367489	CHRG BASE RADIO INST&COMS AZIMUTH	1	EA	- each		
					Net value of item	250.00	250.00

Base Station Radio Installation & Commissioning inclusive of DC power cable and Multimode armoured fiber cable , grounding cable laying and End Termination of MM armoured fiber cable with SFP both end , grounding cable(6 MM^2 X1C) and DC power cable(2CX14 AWG) . All FIM and Details Mentioned Below.#Installing, fixing, assembling, interconnecting of Base radio with mounting bracket at recommended height and Azimuth as per RJIO guideline. Base radio shall be installed on RJIO tower infra or building terrace pole mount.#Commissioning of Base radio and tilt/ alignment to get desire RSL as per link engineering.#Configure the BS Radio to integrate with RJIL EMS system successfully. #Proper weather proofing to be applied on all cable connectors at Radio end.#Material : Laptop to be provided by vendor (Required till ZTP is ready)#(I&C to be done as per installation guidelines released for the Products to be deployed)#BS Radio dimension : H490xW295xD75mm , weight : 4Kg #Termination of cable and SFP is part of deployment vendor scope#Material : Base Radio with accessories (wt. 4 Kg approx.) & IRM KIT (FIM: UBR Equipments & IRM KIT)"

40	3367548	CHRG LAY & ROUTING-MULTIMODE FIBER CABLE	60	M	- Meter		
					Net value of item	5.00	300.00

Laying and routing of MultiMode fiber cable through Cable tray and termination of pigtail with SFP on Radio and L2 switch optical port#FIM -Average length of Multi Mode armoured fiber cable provided by OEM is 50 to 100m per site. RJIO will provide 10G SFP to connect at Radio and L2 switch end.#Termination of the cables is part of TSP contractor scope#Material : Crimping tool to be provided by vendor if required."

50	3137158	LAYING-2CX2.5SQMM COPPER FLEXIBLE CABLE	60	M	- Meter		
					Net value of item	15.00	900.00

Laying of 2Cx2.5Sqmm copper flexible cable

60	3317347	SITC 1CX6 SQMM CU CBL YY FRLSH	5	M	- Meter		
					Net value of item	75.00	375.00

"SUPPLY, INSTALLATION, TESTING & COMMISSIONING OF ELECTRICAL CABLES WITH NECESSARY HARDWARES LIKE CLAMPS, CABLE TYE, GLANDS, LUGS, IDENTIFICATION TAGS ETC. #TYPE OF CABLE : 1CX6 SQMM CU CBL YY FRLSH.

70	3269867	TERMINATION OF CABLE 1CX6 SQMM Y	4.000	NOS	- No.		
					Net value of item	48.00	192.00

TERMINATION OF 1CX6 SQMM Y.AS PER SYSTEM REQUIREMENT.,
SLEEVING,
FERRULING, TAGGING AS PER STANDARD TELECOM PRACTICES.

80	3367739	CHRG ATP-11A - WIFI A6 DEPLOYMENT	1	EA	- each		
					Net value of item	750.00	750.00

Charges for Installation & Commissioning (ATP-11A) Acceptance and Site CMM (Chief Maintenance Manager) Handover using tools provided as per the guidelines of engineer in charge along with 100% compliance and completion with as built drawings, testing and commissioning reports as per the requirement [ATP = Acceptance Test Procedure]##a. Charges for field acceptance (ATP-11A/C) using the assigned tools.#b. Capturing of the Radio installation pictures along with its exact location.#c. Power and grounding cable laying and termination to be captured.#d. weather proofing at radio end to be captured#e. Charges for execution of commissioning tests (ATP-11C) using the assigned tools.#f. Throughput/Ping and Latency Tests to be carried at each Radio.#g. CMM Handover to be carried within 30 days of Site ATP-11A completion for milestone closure#h. The rate shall include the cost of manpower, all software & hardware tools and tackles, required to execute the job.#i. Scope includes Site mobilization charges#* In case of deviation, NPE approval required for any additional vendor support required.#**Milestone closure can only be acceptable post completion and relevant approvals. All changes post rejection need to be closed within the scope requirement without any additional charges"#(The Unit of Measurement is "Per Site basis")

90	3367713	CHRG ATP-11C - WIFI A6 DEPLOYMENT	1	EA	- each		
					Net value of item	750.00	750.00

Charges for Installation & Commissioning (ATP-11C) Acceptance and Site CMM (Chief Maintenance Manager) Handover using tools provided as per the guidelines of engineer in charge along with 100% compliance and completion with as built drawings, testing and commissioning reports as per the requirement [ATP = Acceptance Test Procedure]##a. Charges for field acceptance (ATP-11A/C) using the assigned tools.#b. Capturing of the Radio installation pictures along with its exact location.#c. Power and grounding cable laying and termination to be captured.#d. weather proofing at radio end to be captured#e. Charges for execution of commissioning tests (ATP-11C) using the assigned tools.#f. Throughput/Ping and Latency Tests to be carried at each Radio.#g. CMM Handover to be carried within 30 days of Site ATP-11A completion for milestone closure#h. The rate shall include the cost of manpower, all software & hardware tools and tackles, required to execute the job.#i. Scope includes Site mobilization charges#* In case of deviation, NPE approval required for any additional vendor support required.#**Milestone closure can only be acceptable post completion and relevant approvals. All changes post rejection need to be closed within the scope requirement without any additional charges"#(The Unit of Measurement is "Per Site basis")

100	3383067	CHRG APPLY PUFF SEALENT AT CABLE ENTRY	1	EA	- each		
					Net value of item	350.00	350.00

Charges for supply & applying of Puff Sealant of approved make on DC Power Cable and CIPRI Cable entry point (Roxtec or equivalent). #The Puff Sealant should be applied properly as per the instructions of the Engineer in Charge to ensure avoidance of any seepage.#(UoM : Nos of cable entry Points)

No	Item Code	Material/Work Description	Quantity	UOM	Price Details	Unit Rate			Amount (INR)
4		A6 I&C_I-UE-TLHR-ENB-9006	1	AU					
					Value of Work			INR/AU	9,647.00
					CGST		9.00	%	868.23
					SGST		9.00	%	868.23
		Service Accounting Number: 998736							

The item covers the following Work :

10 3269867 TERMINATION OF CABLE 1CX6 SQMM Y 4.000 NOS - No.
Net value of item 48.00 192.00

TERMINATION OF 1CX6 SQMM Y.AS PER SYSTEM REQUIREMENT.,
SLEEVING,
FERRULING, TAGGING AS PER STANDARD TELECOM PRACTICES.

20 3317347 SITC 1CX6 SQMM CU CBL YY FRLSH 5 M - Meter
Net value of item 75.00 375.00

"SUPPLY, INSTALLATION, TESTING & COMMISSIONING OF ELECTRICAL CABLES WITH NECESSARY HARDWARES LIKE CLAMPS, CABLE TYE, GLANDS, LUGS, IDENTIFICATION TAGS ETC. #TYPE OF CABLE : 1CX6 SQMM CU CBL YY FRLSH.

30 3137158 LAYING-2CX2.5SQMM COPPER FLEXIBLE CABLE 60 M - Meter
Net value of item 15.00 900.00

Laying of 2Cx2.5Sqmm copper flexible cable

40 3367548 CHRG LAY & ROUTING-MULTIMODE FIBER CABLE 60 M - Meter
Net value of item 5.00 300.00

Laying and routing of MultiMode fiber cable through Cable tray and termination of pigtail with SFP on Radio and L2 switch optical port#FIM -Average length of Multi Mode armoured fiber cable provided by OEM is 50 to 100m per site. RJIO will provide 10G SFP to connect at Radio and L2 switch end.#Termination of the cables is part of TSP contractor scope#Material : Crimping tool to be provided by vendor if required."

50 3367489 CHRG BASE RADIO INST&COMS AZIMUTH 1 EA - each
Net value of item 250.00 250.00

Base Station Radio Installation & Commissioning inclusive of DC power cable and Multimode armoured fiber cable , grounding cable laying and End Termination of MM armoured fiber cable with SFP both end , grounding cable(6 MM^2 X1C) and DC power cable(2CX14 AWG) . All FIM and Details Mentioned Below.#Installing, fixing, assembling, interconnecting of Base radio with mounting bracket at recommended height and Azimuth as per RJIO guideline. Base radio shall be installed on RJIO tower infra or building terrace pole mount.#Commissioning of Base radio and tilt/ alignment to get desire RSL as per link engineering.#Configure the BS Radio to integrate with RJIL EMS system successfully. #Proper weather proofing to be applied on all cable connectors at Radio end.#Material : Laptop to be provided by vendor (Required till ZTP is ready)#(I&C to be done as per installation guidelines released for the Products to be deployed)#BS Radio dimension : H490xW295xD75mm , weight : 4Kg #Termination of cable and SFP is part of deployment vendor scope#Material : Base Radio with accessories (wt. 4 Kg approx.) & IRM KIT (FIM: UBR Equipments & IRM KIT)"

60 3397253 CHRG EXTRA TRANSPORT CHRG>50 KM (PICKUP) 214 KM - Kilometer
Net value of item 20.00 4,280.00

EXTRA TRANSPORTATION COST BEYOND 50 KM FOR FIM MATERIAL FROM W/H TO SITE LOADING , UNLOADING, HANDLING ETC. WITH SMALL COMMERCIAL VEHICLE (PICKUP OR EQUIVALENT).

70 3397271 CHRG TRANSPORT-UPTO 50KM-SCV-2-3SITE MAT 1 EA - each
Net value of item 1,500.00 1,500.00

Transportation Charges for Free Issue Material (FIM) from W/H to the Site with SCV (Pickup or equivalent).Charges are inclusive of Loading, Unloading, handling, Toll, etc.This Service Code is applicable when Material of Multiple (2-3) Sites is carried in One Trip(Rate per Site basis)

80 3367739 CHRG ATP-11A - WIFI A6 DEPLOYMENT 1 EA - each
Net value of item 750.00 750.00

Charges for Installation & Commissioning (ATP-11A) Acceptance and Site CMM (Chief Maintenance Manager) Handover using tools provided as per the guidelines of engineer in charge along with 100% compliance and completion with as built drawings, testing and commissioning reports as per the requirement [ATP = Acceptance Test Procedure]##a. Charges for field acceptance (ATP-11A/C) using the assigned tools.#b. Capturing of the Radio installation pictures along with its exact location.#c. Power and grounding cable laying and termination to be captured.#d. weather proofing at radio end to be captured#e. Charges for execution of commissioning tests (ATP-11C) using the assigned tools.#f. Throughput/Ping and Latency Tests to be carried at each Radio.#g. CMM Handover to be carried within 30 days of Site ATP-11A completion for milestone closure#h. The rate shall include the cost of manpower, all software & hardware tools and tackles, required to execute the job.#i. Scope includes Site mobilization charges#* In case of deviation, NPE approval required for any additional vendor support required.#**Milestone closure can only be acceptable post completion and relevant approvals. All changes post rejection need to be closed within

No	Item Code	Material/Work Description	Quantity	UOM	Price Details	Unit Rate	Amount (INR)
the scope requirement without any additional charges"#(The Unit of Measurement is "Per Site basis")							
90	3367713	CHRG ATP-11C - WIFI A6 DEPLOYMENT	1	EA	- each		
					Net value of item	750.00	750.00

Charges for Installation & Commissioning (ATP-11C) Acceptance and Site CMM (Chief Maintenance Manager) Handover using tools provided as per the guidelines of engineer in charge along with 100% compliance and completion with as built drawings, testing and commissioning reports as per the requirement [ATP = Acceptance Test Procedure]##a. Charges for field acceptance (ATP-11A/C) using the assigned tools.#b. Capturing of the Radio installation pictures along with its exact location.#c. Power and grounding cable laying and termination to be captured.#d. weather proofing at radio end to be captured#e. Charges for execution of commissioning tests (ATP-11C) using the assigned tools.#f. Throughput/Ping and Latency Tests to be carried at each Radio.#g. CMM Handover to be carried within 30 days of Site ATP-11A completion for milestone closure#h. The rate shall include the cost of manpower, all software & hardware tools and tackles, required to execute the job.#i. Scope includes Site mobilization charges#* In case of deviation, NPE approval required for any additional vendor support required.#**Milestone closure can only be acceptable post completion and relevant approvals. All changes post rejection need to be closed within the scope requirement without any additional charges"#(The Unit of Measurement is "Per Site basis")

100	3383067	CHRG APPLY PUFF SEALENT AT CABLE ENTRY	1	EA	- each		
					Net value of item	350.00	350.00

Charges for supply & applying of Puff Sealant of approved make on DC Power Cable and CIPRI Cable entry point (Roxtec or equivalent). #The Puff Sealant should be applied properly as per the instructions of the Engineer in Charge to ensure avoidance of any seepage.#(UoM : Nos of cable entry Points)

5		A6 I&C_I-UE-TLSP-ENB-T002	1	AU			
					Value of Work	INR/AU	9,727.00
					CGST 9.00	%	875.43
					SGST 9.00	%	875.43
		Service Accounting Number: 998736					

The item covers the following Work :

10	3137158	LAYING-2CX2.5SQMM COPPER FLEXIBLE CABLE	60	M	- Meter		
					Net value of item	15.00	900.00

Laying of 2Cx2.5Sqmm copper flexible cable

20	3317347	SITC 1CX6 SQMM CU CBL YY FRLSH	5	M	- Meter		
					Net value of item	75.00	375.00

"SUPPLY, INSTALLATION, TESTING & COMMISSIONING OF ELECTRICAL CABLES WITH NECESSARY HARDWARES LIKE CLAMPS, CABLE TYE, GLANDS, LUGS, IDENTIFICATION TAGS ETC. #TYPE OF CABLE : 1CX6 SQMM CU CBL YY FRLSH.

30	3269867	TERMINATION OF CABLE 1CX6 SQMM Y	4.000	NOS	- No.		
					Net value of item	48.00	192.00

TERMINATION OF 1CX6 SQMM Y.AS PER SYSTEM REQUIREMENT.,
SLEEVING,
FERRULING, TAGGING AS PER STANDARD TELECOM PRACTICES.

40	3367739	CHRG ATP-11A - WIFI A6 DEPLOYMENT	1	EA	- each		
					Net value of item	750.00	750.00

Charges for Installation & Commissioning (ATP-11A) Acceptance and Site CMM (Chief Maintenance Manager) Handover using tools provided as per the guidelines of engineer in charge along with 100% compliance and completion with as built drawings, testing and commissioning reports as per the requirement [ATP = Acceptance Test Procedure]##a. Charges for field acceptance (ATP-11A/C) using the assigned tools.#b. Capturing of the Radio installation pictures along with its exact location.#c. Power and grounding cable laying and termination to be captured.#d. weather proofing at radio end to be captured#e. Charges for execution of commissioning tests (ATP-11C) using the assigned tools.#f. Throughput/Ping and Latency Tests to be carried at each Radio.#g. CMM Handover to be carried within 30 days of Site ATP-11A completion for milestone closure#h. The rate shall include the cost of manpower, all software & hardware tools and tackles, required to execute the job.#i. Scope includes Site mobilization charges#* In case of deviation, NPE approval required for any additional vendor support required.#**Milestone closure can only be acceptable post completion and relevant approvals. All changes post rejection need to be closed within the scope requirement without any additional charges"#(The Unit of Measurement is "Per Site basis")

50	3367713	CHRG ATP-11C - WIFI A6 DEPLOYMENT	1	EA	- each		
					Net value of item	750.00	750.00

Charges for Installation & Commissioning (ATP-11C) Acceptance and Site CMM (Chief Maintenance Manager) Handover using tools provided as per the guidelines of engineer in charge along with 100%

No	Item Code	Material/Work Description	Quantity	UOM	Price Details	Unit Rate	Amount (INR)

compliance and completion with as built drawings, testing and commissioning reports as per the requirement [ATP = Acceptance Test Procedure]##a. Charges for field acceptance (ATP-11A/C) using the assigned tools.#b. Capturing of the Radio installation pictures along with its exact location.#c. Power and grounding cable laying and termination to be captured.#d. weather proofing at radio end to be captured#e. Charges for execution of commissioning tests (ATP-11C) using the assigned tools.#f. Throughput/Ping and Latency Tests to be carried at each Radio.#g. CMM Handover to be carried within 30 days of Site ATP-11A completion for milestone closure#h. The rate shall include the cost of manpower, all software & hardware tools and tackles, required to execute the job.#i. Scope includes Site mobilization charges#* In case of deviation, NPE approval required for any additional vendor support required.#**Milestone closure can only be acceptable post completion and relevant approvals. All changes post rejection need to be closed within the scope requirement without any additional charges"#(The Unit of Measurement is "Per Site basis")

60	3383067	CHRG APPLY PUFF SEALENT AT CABLE ENTRY	1	EA - each	Net value of item	350.00	350.00

Charges for supply & applying of Puff Sealant of approved make on DC Power Cable and CIPRI Cable entry point (Roxtec or equivalent). #The Puff Sealant should be applied properly as per the instructions of the Engineer in Charge to ensure avoidance of any seepage.#(UoM : Nos of cable entry Points)

70	3367548	CHRG LAY & ROUTING-MULTIMODE FIBER CABLE	60	M - Meter	Net value of item	5.00	300.00

Laying and routing of MultiMode fiber cable through Cable tray and termination of pigtail with SFP on Radio and L2 switch optical port#FIM -Average length of Multi Mode armoured fiber cable provided by OEM is 50 to 100m per site. RJIO will provide 10G SFP to connect at Radio and L2 switch end.#Termination of the cables is part of TSP contractor scope#Material : Crimping tool to be provided by vendor if required."

80	3367489	CHRG BASE RADIO INST&COMS AZIMUTH	1	EA - each	Net value of item	250.00	250.00

Base Station Radio Installation & Commissioning inclusive of DC power cable and Multimode armoured fiber cable , grounding cable laying and End Termination of MM armoured fiber cable with SFP both end , grounding cable(6 MM^2 X1C) and DC power cable(2CX14 AWG) . All FIM and Details Mentioned Below.#Installing, fixing, assembling, interconnecting of Base radio with mounting bracket at recommended height and Azimuth as per RJIO guideline. Base radio shall be installed on RJIO tower infra or building terrace pole mount.#Commissioning of Base radio and tilt/ alignment to get desire RSL as per link engineering.#Configure the BS Radio to integrate with RJIL EMS system successfully. #Proper weather proofing to be applied on all cable connectors at Radio end.#Material : Laptop to be provided by vendor (Required till ZTP is ready)#(I&C to be done as per installation guidelines released for the Products to be deployed)#BS Radio dimension : H490xW295xD75mm , weight : 4Kg #Termination of cable and SFP is part of deployment vendor scope#Material : Base Radio with accessories (wt. 4 Kg approx.) & IRM KIT (FIM: UBR Equipments & IRM KIT)"

90	3397253	CHRG EXTRA TRANSPORT CHRG>50 KM (PICKUP)	218	KM - Kilometer	Net value of item	20.00	4,360.00

EXTRA TRANSPORTATION COST BEYOND 50 KM FOR FIM MATERIAL FROM W/H TO SITE LOADING , UNLOADING, HANDLING ETC. WITH SMALL COMMERCIAL VEHICLE (PICKUP OR EQUIVALENT).

100	3397271	CHRG TRANSPORT-UPTO 50KM-SCV-2-3SITE MAT	1	EA - each	Net value of item	1,500.00	1,500.00

Transportation Charges for Free Issue Material (FIM) from W/H to the Site with SCV (Pickup or equivalent).Charges are inclusive of Loading, Unloading, handling, Toll, etc.This Service Code is applicable when Material of Multiple (2-3) Sites is carried in One Trip(Rate per Site basis)

Total Value of Work	INR	51,475.00
Total CGST	INR	4,632.75
Total SGST	INR	4,632.75
Total Order Value:	**INR**	**60,740.50**

Terms of payment :

Payment shall be made as per Detailed Payment Terms specified in the purchasing document.

Vendor will ensure that Tax Invoice is uploaded on EBIZ portal of Buyer within 7 days of its issue, Failure to upload the Tax Invoice within 7 days will be considered as non - submission of Invoice

Vendor Bank Details:
Bank Account No. : 105701601000515
Bank Name : UNION BANK OF INDIA
City : GAUTAM BUDDHA NAGAR

Liquidated Damages :

0.5 % PER WEEK TO MAX OF 5%

Document Submission Bank:

Note(S): 1. It is essential that the Contractor shall mention ItemNo. & Item code along with corresponding Material/Work Description and W.O.No. as mentioned above, in the Delivery challan (On-Shore Order), Measurement sheet and invoice for ease of material Inwarding, Certification of work and Bill Processing. Failure to do so may be the grounds for the rejections(s) or delay in release of payment(s).

PLANT REGISTRATION NO. : 09AAACR5055K1Z5

RELIANCE PROJECTS & PROPERTY MANAGEMENT SERVICES LIMITED
C/o Reliance Industries Ltd, II floor, Trade Tower 94,
M.G.Marg Hazaratganj, Lucknow-226 001, UTTAR PRADESH, INDIA
Telephone : 9140955115 Email: Ashwini1.Singh@ril.com

Purchase Order

Number : P16/630343554
Date : 19.02.2026

BILL To ANNEXURE

Bill To Address : (Plant) JP79

RIL Proj-Uttar Pradesh (E),Reliance Industries Ltd.,,
8 and 9, PLOT NO TC 58V AND 59V,ELDECO CORPORATE,CHAMBER 2, PHASE 1,VIBHUTI KHAND, GOMTI NAGAR
Lucknow-226010
Uttar Pradesh,India
GSTIN:09AAACR5055K1Z5

POSrNo	Short Description
1	A6 I&C_I-UE-ORAI-ENB-9005
2	A6 I&C_I-UE-SIKN-ENB-9031
3	A6 I&C_I-UE-TLBT-ENB-9091
4	A6 I&C_I-UE-TLHR-ENB-9006
5	A6 I&C_I-UE-TLSP-ENB-T002

RELIANCE PROJECTS & PROPERTY MANAGEMENT SERVICES LIMITED
C/o Reliance Industries Ltd, II floor, Trade Tower 94,
M.G.Marg Hazaratganj, Lucknow-226 001, UTTAR PRADESH, INDIA
Telephone : 9140955115
Email: Ashwini1.Singh@ril.com

Number P16 / 630343554
Date 19.02.2026

Additional terms and Conditions of the Work Order / Service Order / Contract Orders /Purchase Orders (hereinafter referred to as Order(s)).

This Order is being issued by Reliance Projects and Property Management Services Limited **("RPPMSL")** on behalf of Reliance Industries Limited **("RIL")** in favour of the entity referred to as Seller / Contractor / Service Provider/ Vendor as the case may be in the respective Order, subject to the following additional terms and conditions, which shall form an integral part of the Order.

1. Seller / Contractor / Service Provider/Vendor hereby agrees and acknowledges that pursuant to a Scheme of Arrangement between **Reliance Projects and Property Management Services Limited ("RPPMSL"/" Demerged Company") and Reliance Industries Limited ("RIL"/" Resulting Company")** and their respective shareholders and creditors, for demerger of Digital, Engineering, Procurement, and Construction**("EPC")**, Infrastructure and other businesses of **RPPMSL** into <B1 RIL on a going concern basis **("Scheme")** approved by Hon'ble NCLT, Mumbai and Ahmedabad respectively in proceedings under **C.P.(CAA)/194/MB/2023 in C.A. (CAA)/116/MB/2023 filed by RIL and Proceedings under CP(CAA)/21(AHM)2023 in CA(CAA)/34(AHM)2023 filed by RPPMSL,** the digital, EPC and infrastructure business of RPPMSL together with all relevant contracts, Orders are demerged and vested with RIL as a going concern with effect from the Effective Date specified in the Scheme.
2. As a matter of convenience and part of transition arrangement pursuant to a separate agreement entered between RIL & RPPMSL, this Order is being issued by RPPMSL on behalf of RIL and will be enforceable by RIL in any manner, in terms of the Order, without any further assignment in this regard.
3. Contractor shall ensure compliance of all applicable laws including applicable labour laws. If RPPMSL is required to bear any cost or consequences of any non-compliance of applicable laws or provisions of this Order by the Contractor / its Sub Contractor as applicable the same shall be recovered from the Contractor without any restriction or limitation.
4. Seller / Contractor / Service Provider / Vendor shall raise correct and complete invoices on RIL and submit all invoices together with necessary supporting(s) as per the terms of the Order and payment will be made by RIL as per the terms of Order. In case any invoices are already raised before RPPMSL after the effective date of the Scheme approved by NCLT, a revised invoice shall be raised on RIL and to be re-submitted along with all supporting documents as required.
5. These additional terms and conditions shall form an integral part of the Order and in case of any conflict between these terms and conditions and other terms and condition of the Order, these terms and conditions shall prevail.
6. In case any clarifications are required the Seller/ Contractor/ Vendor/ Service Provider shall approach RIL or Engineer In Charge (EIC)/ contract person of RIL specified in the Order, and the clarifications if any issued by RIL shall be final and binding on the Seller/ Contractor/ Service Provider/ Vendor.